

HAPPY FISH GRID-CONNECTED SOLAR PV BUNDLE PROJECT - SLCCS
VERSION 1.0

Client	Global Sea Foods (Pvt) Ltd
Completion Date of the Verification Report	15/07/2024
Version No.	02
Country	Sri Lanka
Monitoring Period	01/01/2021 to 31/12/2023
Estimated SCER in this monitoring period	1,125 tCO ₂ e
Verified SCER	1,051 tCO ₂ e
Contact details	Mr. Nayanajith De Silva Senior Manager Quality Assurance Tel: +94775109253 E-mail: nayanajith@gsffish.com
Summary of the verification report	
Validation and Verification Division of Sri Lanka Climate Fund has performed the verification of the emission reductions for the “Happy Fish Grid-connected Solar PV Bundle Project (two units)”, operating under Global Sea Foods (Pvt) Ltd., for the period from 01/01/2021 to 31/12/2023. It is our verification opinion that the GHG emission reductions reported for the project in the monitoring report (Version 02) of 25th May 2024 are fairly stated. The GHG emission reductions were calculated correctly on the basis of the approved monitoring methodology AMS-I.D(version 18), 2014 and meets all relevant SLCCS requirements. Sri Lanka Climate Fund is verified that the emission reductions from “Happy Fish Grid-connected Solar PV Bundle Project” in Sri Lanka during the period from 01/01/2021 to 31/12/2023 is 1,051 tons of CO₂ equivalent.	
Project Title	Happy Fish Grid-connected Solar PV Bundle Project (Unit 1 and unit 2)
Report No	SLCCS/VRR/0012/2024/03
Work carried out by	Validation and Verification Division Sri Lanka Climate Fund (Pvt) Ltd
Work Approved by	Mrs. Harshani Abeyrathna Chief Executive Officer Sri Lanka Climate Fund (Pvt) Ltd
No of Pages	17

CONTENT

1	INTRODUCTION	4
1.1	Objective	4
1.2	Scope and criteria	4
1.3	Description of the Project Activity	4
1.4	Methodology for Determining Emission Reductions	4
2	Methodology	5
	Verification Team	5
2.1.	Publication of the monitoring report for public review	5
2.2.	Desk review of monitoring report and supporting documents	6
2.3.	On- site inspections	6
2.4.	Internal technical review	7
2.5.	Reporting of Findings	7
3.	Verification Findings	7
3.1.	Remaining issues (FARs) from previous validation or verification	7
3.2.	Monitoring report	8
3.3.	Project implementation	8
3.4.	Post registration changes	8
3.5.	Methodology for determining Emission Reductions	8
3.5.1.	Applicability	8
3.5.2.	Compliance of the monitoring plan with the monitoring methodology and applicable methodological tools	8
3.5.3.	Compliance of monitoring with monitoring plan	9
3.5.4.	Assessment of data and calculation of emission reductions	10
3.5.5.	Accuracy of emission reduction calculations	10
3.5.6.	Management system and quality control	11
4.	VERIFICATION OPINION	13
5.	REFERENCE	18
6.	APPENDIX : Verification Team	19

ABBREVIATIONS

BE	Baseline Emissions
CAR	Corrective Action Request
CDM	Clean Development Mechanism
CEB	Ceylon Electricity Board
CL	Clarification Request
CMA	Carbon Management Assessment
CO ₂	Carbon dioxide
CO ₂ e	Carbon dioxide equivalent
FAR	Forward Action Request
GHG(s)	Greenhouse Gas(es)
GWP	Global Warming Potential
MR	Monitoring Report
PE	Project Emission
PP(s)	Project Participant(s)
SCER(s)	Sri Lanka Certified Emission Reduction(s)
SLCCS	Sri Lanka Carbon Crediting Scheme
SLCFVAL	Validation Division of Sri Lanka Climate Fund
SLSEA	Sri Lanka Sustainable Energy Authority
VVS	Validation and Verification Standard

1 INTRODUCTION

Global Sea Foods (Pvt) Ltd., has requested Sri Lanka Climate Fund (SLCF) to carry out the verification and certification of emission reductions reported for the “Happy Fish Grid-connected Solar PV Bundle Project – unit 01 and unit 02” in the period from 01/01/2021 to 31/12/2023. This report contains the findings from the verification and a certification statement for the Sri Lankan Certified Emission Reductions (SCERs).

1.1 Objective

The objective of this verification was to verify emission reductions reported for the Happy Fish Grid-connected Solar PV Bundle Project in Sri Lanka for the period from 01/01/2021 to 31/12/2023. The information included in the Monitoring Report and the supporting documents were verified against the requirements as set out by the SLCCS.

1.2 Scope and criteria

The verification scope is given as a thorough independent and objective assessment of the monitoring report including especially:

- To verify that actual monitoring systems and procedures are in compliance with the monitoring systems and procedures described in the monitoring plan.
- To evaluate the GHG emission reduction data and express a conclusion with a reasonable level of assurance about whether the reported GHG emission reduction data is free from material misstatement.
- To verify that reported GHG emission reduction data is sufficiently supported by evidence.
- To ensure that reported emission reductions are complete and accurate in accordance with SLCCS criteria.

1.3 Description of the Project Activity

Title of the Project Activity	Happy Fish Grid-connected Solar PV Bundle Project (unit 01 and unit 02)
Project Participant(s)	Global Sea Foods (Pvt) Ltd
Host Party(ies)	Sri Lanka
Monitoring Methodology	AMS I.D. /Version 18/EB 81, 2014
Project's crediting period	01/01/2021 to 31/12/2027
Period verified in this verification	01/01/2021 to 31/12/2023

1.4 Methodology for Determining Emission Reductions

Global Sea Foods (Pvt) Ltd. has implemented grid connected solar PV bundle project with the total cumulative capacity of 613.7 kWp in two plants of Global Sea Foods (Pvt) Ltd., Existing grid-connected roof top solar PV power plants located at Badalgama in Gampaha district. The project activity which involves installation of solar photovoltaic (SPV) and generated electricity is supplied to the national electricity grid of Sri Lanka. As per the validated CMA, the annual estimated energy generation of the project is 557.8 MWh.

The project was registered as a bundle renewable energy project complying the methodological requirements of Sectoral scope 1, Type I, AMS-I.D Grid connected renewable electricity generation, Version 18.0,2014. As per the validated CMA, the expected annual GHG emission reduction resulting in the operation of project is 375 tCO₂e and the expected total GHG emission reductions in the first monitoring period is 1,125 tCO₂e.

The project's emission reductions are calculated by multiplying the net electricity generated by the project with the grid emission factor. According to the validated CMA, there are no project emissions and leakage emissions to deduct from the emission reductions of this monitoring period and it is verified and found to be in order.

2 METHODOLOGY

Verification was conducted using SLCCS procedures in line with the requirements specified in the CDM Modalities and Procedures, the latest version of the CDM Validation and Verification Standard. The verification consisted of the following phases:

- Appointment of team members and technical reviewers
- Publication of the monitoring report
- Verification planning
- Desk review of the monitoring report and supporting documents
- On-Site assessment
- Background investigation and follow-up interviews with personnel of the project developer and its contractors
- Draft verification reporting
- The resolution of outstanding issues and corrective actions (if any)
- Final verification reporting
- Technical review
- Final approval of the certification

The verification of the emission reductions has assessed all factors and issues that constitute the basis for emission reductions from the project. These include:

- Net electricity supplied to the national grid on a monthly basis
- Grid emission factor

Verification Team

On the basis of a competence analysis and individual availabilities, a verification team, consisting of one team leader, one technical expert, two team members, and one internal

technical reviewer were appointed. Qualifications of the verification team are summarized in the Appendix.

Name	Company	Role	Task Performed
Eng. Chamara Ariyathilaka	Sri Lanka Climate Fund (Pvt) Ltd	TL / TE	☒ DR ☒ SV ☒ RI ☐ TR
Ms. Mananda Wijayanayake	Sri Lanka Climate Fund (Pvt) Ltd	TM	☒ DR ☒ SV ☐ RI ☐ TR
Mrs. Madhubhashini Gunathilaka	Sri Lanka Climate Fund (Pvt) Ltd	TM	☒ DR ☒ SV ☐ RI ☐ TR
Mrs. Wageesha Alankara	Sri Lanka Climate Fund (Pvt) Ltd	ITR	☐ DR ☐ SV ☐ RI ☒ TR

TL -Team Leader TM- Team Member TE- Technical Expert ITR- Internal Technical Reviewer
SV- Site Visit RI- Report Issuance DR- Document Review TR- Technical Review

The verification team fulfils the following requirements:

- qualification for all technical area/s (TAs) related to the activity;
- technical experts who provide specific technical, methodological and sectoral knowledge and/or expertise and qualification for TAs can be involved;
- it includes one Team Leader that takes the responsibility to lead the team;
- it includes a Team Member/Verifier;
- at least one member who performs the on-site visit is qualified for all TAs related to the activity;
- at least one member who performs the on-site visit is qualified as Team Leader, even if he/she does not cover this role for the specific activity;
- the same person can cover more than one role.

2.1 Publication of the monitoring report for public review

According to the SLCCS requirement, the draft MR as received from the project participants, has been made publicly available on the dedicated SLCCS website prior to the verification activity commenced. The public has been invited to comment on the MR during the 30-day public comment period.

No comments were received for the monitoring report.

2.2 Desk review of monitoring report and supporting documents

The monitoring reports (Version 01 and 02), the emission reduction calculations, provided in the form of spreadsheets submitted by Global Sea Foods (Pvt) Ltd., were assessed as a part of the verification.

In addition to the monitoring documentation provided by the project participants, verification team reviewed:

1. The registered Carbon Management Assessment, the monitoring plan contained in the CMA as well as the validation report.
2. The applied monitoring methodology AMS-I.D. (version 18.0), EB 81, 2014
3. Other operational documents (Calibration procedure, Data monitoring procedure) as evidence during the site visit

2.3 On- site inspections

On 14th February 2024, SLCF carried out site visit at the project site. SLCF verified that the actual implementation and operation of the project is as described in the CMA. The electricity meters used for monitoring electricity (including the calibration records) were checked. Evidence for the reported net generation of electricity was verified.

As part of the on-site inspection, following personnel were interviewed to further verify the documented information.

Name	Designation	Organization/Entity	Method (Face to face/ Telephone)	Main topics covered
Mr. P.A. Gayan Buddhika Karunaratna	Engineer Service marketing	Sunpower Renewables (Pvt) Ltd	Face to Face	Technical Specifications of Solar Project, Online Monitoring System, Incident reporting and failures
Mr. L.D. Nayanajith De Silva	Senior Quality Assurance Manager	Global Sea Food (Pvt) Ltd	Face to Face	Data Gathering – QA/QC procedure, reporting and emission reduction calculations
Mr. T.S.T. Siriwardhana	Maintenance Incharge	Global Sea Food (Pvt) Ltd	Face to Face	Regular Maintenance and operations- Disaster recovery, personnel engaged in monitoring Activities.

2.4 Independent review

Monitoring report submitted by Global Sea Foods (Pvt) Ltd. and additional background documents related to the CMA and MR were Verified. Furthermore, the verification team used additional documentation like Regulations, technical specifications referring to the MR to the basic conditions and technical data.

The technical reviewer verified the entire report before submission. The technical reviewer is a competent GHG auditor being appointed for the scope this project falls under.

The verification team and the technical reviewer have the collective competence necessary to perform the verification.

2.5 Reporting of Findings

A **Clarification Request (CL)** is raised where information is insufficient, unclear or not transparent enough to establish whether the applicable SLCCS requirements have been met.

A **Corrective Action Request (CAR)** is issued where:

- Non-conformities with the monitoring plan or methodology are found in monitoring and reporting, or if the evidence provided to prove conformity is insufficient;
- Mistakes have been made in assumptions, application of the methodology or the project documentation which will have a direct influence the project results,
- The requirements deemed relevant for verification of the project with certain characteristics have not been met or
- There is a risk that the project would not be registered by the SLCCS or that emission reductions would not be able to be verified and certified.

A **Forward Action Request (FAR)** is issued for actions if the monitoring and reporting require attention and/or adjustment for the next verification period.

3. VERIFICATION FINDINGS

This section describes the findings from the verification of the emission reductions reported for the Happy Fish Grid-connected Solar PV Bundle Project for the period from 01/01/2021 to 31/12/2023.

3.1. Remaining issues (FARs) from previous validation or verification

According to the validation report (version 01) no issues were required to be closed out during the initial verification. This has been confirmed from the validation report and registered CMA and during the site visit.

3.2. Monitoring report

The monitoring report for the project activity, Happy Fish Grid-connected Solar PV Bundle Project Version 02 of 25/05/2024 submitted by Global Sea Foods (Pvt) Ltd., has been the basis for the verification process. Verification Team confirms that the above submitted MR is based on the currently valid MR template of SLCCS version 03.0 and is completed in accordance with the applicable CDM methodology (AMS-I.D. (version 18.0, EB 81, 2014).

3.3. Project implementation

The two projects were implemented and commissioned on following dates,

Unit No	Site Location	Project Commissioning date
Unit 01	Perawalawatta, Badalgama.	26.02.2020
Unit 02	171/C/11, Beatrice Estate, Badalgama.	23.04.2021

First monitoring period (01/01/2021 to 31/12/2023) was within the eligible crediting period.

Actual implementation of the registered project activity is installation of a 613.7 kW solar power project at two different locations of Global Sea Foods (Pvt) Ltd, at Badalgama, as per the CMA Version 02 dated 15/05/2024.

The details of the solar generation systems with respect to installation and capacity have been verified to be consistent with description indicated in the CMA. The actual implementation of the project during this verification period was verified from name plate capacities of each equipment and their accuracy levels.

3.4. Methodology for determining Emission Reductions

3.4.1. Applicability

The project falls under Type I: Renewable Energy Projects and rightly applies the approved methodology AMS-I.D., Grid connected renewable electricity generation, Version 18.0, EB 81, 2014 (Small scale)

All criteria for applicability of selected methodology are fulfilled. The project is a grid connected solar power project and is confirmed from approval from Ceylon Electricity Board. The project activity is a Greenfield project activity resulting in the generation of

renewable energy.

3.4.2. Compliance of the monitoring plan with the monitoring methodology and applicable methodological tools

During this monitoring period, the validated and registered CMA was found in accordance with the applied methodology, AMS-I.D version 18.0. All monitoring parameters, monitoring and calibration procedures follow the methodology requirements.

3.4.3. Compliance of monitoring with monitoring plan

The following parameters have been monitored in accordance with the monitoring plan in the registered CMA and the monitoring report.

Data/ Parameter	Source of Data	Reported value for the project period
Combined Margin CO ₂ Emission Factor	Sri Lanka Sustainable Energy Authority	0.7079 tCO ₂ e/MWh (year 2021)
Net Energy Exported to CEB	CEB invoices	1,485.30 MWh (January 2021 – December 2023)

3.4.4. Data and parameters monitored ex-post

Data / Parameter	Net Electricity Supplied to the grid ($EG_{p,j,y}$)
Frequency of measuring/recording	Monthly
Is measuring and reporting frequency in accordance with the monitoring plan and monitoring methodology? (Yes / No)	Yes
Monitoring equipment	Energy meter Accuracy class of the meter- class 01
Calibration frequency/interval	Annual
Is the calibration interval in line with the monitoring plan of the CMA?	Yes, the calibration frequency indicated in the CMA is “Annual”. The calibration frequency was verified during the verification.
Company performing the calibration	CEB
Did calibration confirm proper functioning of monitoring equipment? (Yes/No)	Yes

Does the calibration cover the monitoring period?	Yes.
How were the values in the monitoring report verified?	The following documents have been Checked: 1. The monthly statements on net electricity supplied to the grid. 2. Invoices raised by the PP to CEB
Does the data management (from monitoring equipment to emission reduction calculation) ensure correct transfer of data and reporting of emission reductions and are necessary QA/QC processes in place?	Yes

3.4.5. Assessment of data and calculation of emission reductions

Availability of the data

The data for all the monitoring parameters have been correctly measured, recorded according to the applied monitoring methodology AMS-I.D, version 18 and the registered CMA. All the data are available for this monitoring period.

Cross-check reported data

Baseline Emissions

The baseline emission for the project activity has been calculated as per the CMA version 02 dated 15/05/2024 and AMS-I.D, version 18. As stated in the section 3.4.3 above, the net electricity generation measured during the monitoring period is 1,485.30 MWh and the measurement is in line with the clause 22 of the methodology. The electricity generation is cross checked from the electricity generation and consumption log book records and there was no any mismatch found to be reported.

As per the clause 18 of the applied methodology AMS-I.D version 18 and calculations as indicated under section 3 of the approved CMA the project participant has calculated the electricity generation based on the export bill issued by CEB, the same has been verified by Verification Team and found to be appropriate.

The net electricity generation to calculate baseline emission found to be 1,485.30 MWh. The baseline emission for the project activity covering the monitoring period worked out based on the approach mentioned above is 1,051 tCO₂e.

Project Emissions

Project emission may include the emissions associated with the project installation, operation and maintenance. As per the methodology applied, these emissions are not significant and attributable to the project activity, hence project emissions are reported as zero.

Leakage Emissions

Not Applicable

Emission Reductions

Therefore, the emission reduction in this monitoring period is:

$$ER_y = BE_y - PE_y - LE_y$$

$$ER_y = 1,051 - 0 - 0 = 1,051 \text{ tCO}_2\text{e}$$

3.4.6. Accuracy of emission reduction calculations

The emission reductions are calculated by multiplying the net electricity exported to the Sri Lankan national grid with the grid emission factor. The electricity exported from the project activities are read directly from an uploading meter. The meter is owned by the CEB and the maintenance and calibration are done by CEB on an annual basis. The calibration certificate covering the entire period has been evidenced.

The data presented in the monitoring report Version 01 and Version 02 were assessed by reviewing in detail project documentation, collection of monitored data, observation of established monitoring and reporting practices and assessment of the reliability of monitoring equipment. It has been verified during the site visit that the monthly electricity generation during the monitoring period has not exceeded the rated capacity for the Happy Fish Grid-connected Solar PV Bundle Project. The emission reductions from the project for the period from 01/01/2021 to 31/12/2023 as reported in the monitoring report of Version 02 dated 25/05/2024 and actually verified at site equals to 1,051 tonnes of CO₂ equivalent. The total emission reductions is 6.58% less than the estimated emission reduction of 1,125 tCO₂e for this monitoring period as per the revised CMA, Version 02.

3.4.7. Management system and quality control

Data was collected based on a data management procedure as described in the registered CMA version 02. The monitoring and reporting of electricity data is in accordance with well-established operational procedures. The site visit confirmed that the management system for the SLCCS project is in place and can be traced, such as the organizational structure with responsibilities, monitoring procedure and monitoring management, emergency treatment procedure and competence criteria of personnel involved in the SLCCS project. The organizational structure and responsibilities have been detailed in the MR for the project activity and were found to be adequate as confirmed during the site visit.

3.4.8. Resolution of Findings

Type of the Finding	☐ CL ☒ CAR ☐ FAR
Finding No	CAR-1
Ref. To MR	Section 4.2
Description of Finding	The reported total exported energy values are not matching with the total of the CEB Bills. Project owner needs to clarify this.
Summary of Project owner response	This has occurred due to a human error occurred while entering electricity export data and the same was corrected in revised MR Version 02.
Verification team Assessment	The revised monitoring report was reviewed by the verification team and confirmed that the error has been corrected. Therefore, the CAR was closed by the verification team.
Conclusion	☐ To be checked during the first periodic verification ☐ Additional action should be taken (finding remains open) ☐ Project documentation was corrected correspondingly ☒ Appropriate action was taken. The finding CAR-1 is closed

Type of the Finding	☐ CL ☒ CAR ☐ FAR
Finding No	CAR-2
Ref. To MR	Section 2.1
Description of Finding	Solar PV system implemented in the units two has only 1 inverter although monitoring report is shown as 4 inverters, and the brand name does not correspond with the other inverters in the Monitoring Report.
Summary of Project owner response	Due to the less exposure to the rule-based mechanism of SLCCS, a clear description has not been provided. Four inverters were replaced due to a failure with one inverter of SMA brand. MR was updated including correct details.

Verification team Assessment	During the verification assessment, the verification team reviewed the corrective actions taken by the project proponent. Four inverters were replaced due to deactivation, and one SMA-brand inverter was added. The Monitoring Report (MR) was updated to include the correct details, accurately reflecting the inverter brand and capacity for Project Unit 2.
Conclusion	☐ To be checked during the first periodic verification ☐ Additional action should be taken (finding remains open) ☐ Project documentation was corrected correspondingly ☒ Appropriate action was taken. The finding CAR-2 is closed

Type of the Finding	☐ CL ☒ CAR ☐ FAR
Finding No	CAR-3
Ref. To MR	Section 4.1
Description of Finding	According to the emission reduction and removals, The grid emission factor doesn't align with the updated value for 2021
Summary of Project owner response	A thorough examination of the terms outlined by SLCCS concerning the updated grid emission factor was conducted. As a result, adjustments were made to accurately reflect the updated grid emission factor from 2021. MR was revised incorporating above correction.
Verification team Assessment	During the verification assessment, the verification team reviewed the corrective actions taken by the project proponent. The project proponent updated the grid emission factor for 2021 in Monitoring Report Version 2 and calculated the emission reductions using the new emission factor.
Conclusion	☐ To be checked during the first periodic verification ☐ Additional action should be taken (finding remains open) ☐ Project documentation was corrected correspondingly ☒ Appropriate action was taken. The finding CAR-3 is closed

4. VERIFICATION OPINION

Sri Lanka Climate Fund (SLCF) has performed the verification of the emission reductions that have been reported for the Happy Fish Grid-connected Solar PV Bundle Project for the period 01/10/2021 to 31/12/2023.

The verification consisted of the following three phases:

- i. desk review of the MR and additional background documents;
- ii. follow-up interviews with project stakeholders;
- iii. resolution of outstanding issues and the issuance of the final validation report and opinion.

It is the responsibility of Verification Team to express an independent verification opinion about the project's conformity with the requirements of SLCCS modalities and procedures and on the reported greenhouse gas emission reductions from the project. SLCF conducted the verification on the basis of the monitoring methodology AMS-I.D. (version 18), the monitoring plan contained in the registered CMA of Happy Fish Grid-connected Solar PV Bundle Project and the monitoring report (Version 02) dated 25/05/2024. The verification included i) checking whether the provisions of the monitoring methodology and the monitoring plan were consistently and appropriately applied and ii) the collection of evidence supporting the reported data.

Based on the interviews, observations, and documental examinations carried out of the site by the verification team,

- the project has been implemented and operated as per the registered CMA;
- the monitoring report and other supporting documents provided are complete and verifiable and in accordance with the applicable SLCCS requirements;
- the monitoring is in place as per the applied baseline and monitoring methodology;
- the monitoring complies with the monitoring plan in the registered CMA;

- the monitoring plan in the registered CMA is as per the applied baseline and monitoring methodology.

In the course of the verification 03 Corrective Action Requests (CARs) were raised and successfully closed and no CLs and FARs were raised.

The review of the CMA and additional documents related to baseline and monitoring methodology; the subsequent background investigation, follow-up interviews and review of comments by parties and stakeholders have provided SLCF Verification Division with sufficient evidence to verify the fulfillment of the stated criteria.

In detail the conclusions can be summarized as follows:

- The project is in line with all legal requirements (Sri Lanka) and all relevant SLCCS requirements for carbon credits. Further the project activity is in compliance with the requirements set up by the applied approved CDM methodology AMS-I.D ver.18

- The monitoring plan is transparent and adequate.
- The calculation of the project emission reductions is carried out in a transparent and conservative manner, so that the calculated emission reductions with a reasonable assurance to be achieved within the crediting period.
- The project full fill all the requirements

SLCF concludes with a reasonable assurance that the GHG emissions reductions of the “Happy Fish Grid-connected Solar PV Bundle Project” for the period 01/01/2021 to 31/12/2023 are fairly stated in the monitoring report (Version 02) dated 25/05/2024.

.....
Mrs. Wageesha Alankara
Internal Technical Reviewer
15/07/2024

.....
Eng. Chamara Ariyathilaka
Team Leader / Technical Expert
15/07/2024

5. REFERENCES

Documents provided by the Project Participants that relate directly to the GHG components of the project. These have been used as direct sources of evidence for the periodic verification conclusions, and are usually further checked through interviews with key personnel.

1. Records of Invoices raised from the project participant for the sale of power
2. Records of Monthly generation details in the plant and maintenance records

Background documents related to the design and/or methodologies employed in the design or other reference documents.

1. AMS-I.D – “Grid connected renewable energy generation”, version 18.0

6. APPENDIX

Verification Team

Eng. Chamara Ariyathilaka	Sri Lanka Climate Fund	Team Leader / Technical Expert B.Sc. (Hons) Engineering (Chemical and Process) He has more than 14 year experience in GHG verification in the industrial sector ranging from service facilities to various industrial processing facilities. He has successfully completed management system ISO 14064 and has been working as the team leader for the verification team of Sri Lanka Climate Fund which has been accredited for organizational GHG verification against ISO 14064-3. Being a project specialist for the GEF funded Bio-Energy Technology Project, he has contributed to develop MRV system for commercial biomass energy generation systems. Further he has engaged in development of project design document for the Clean Development Mechanism (CDM)
Ms. Mananda Wijayanayake	Sri Lanka Climate Fund	Team Member B.Sc. (Hons) degree in Agriculture specializing in Plantation Product Development Technology. She has worked as an environment and climate change consultant at Smallholder Agribusiness Partnership Program. Engage over five Green House Gas verifications (Document review and site visit) and participated 6 farm visits of Nestle program conducted by SLCF.
Mrs. Madhubhashini Gunathilaka	Sri Lanka Climate Fund	Team Member B.Sc. degree in Plantation Management and completed a Higher National Diploma in Agriculture (HNDDT). She has worked as an Agricultural Instructor - Department of Agriculture. She is a Registered Assessor - Tertiary and Vocational Education Commission. Engage over three Green House Gas verifications (Document review and site visit) and participated 6 farm visits of Nestle program conducted by SLCF.

Mrs. Wageesha Alankara	Sri Lanka Climate Fund	Internal Technical Reviewer B.Sc. (Hons) degree in Agriculture specializing in Postharvest Horticulture and completed the Training Programme on Carbon Footprint Assessment for Sustainable Process Industry conducted by University of Moratuwa. She has engaged over 10 verification assessments conducted by SLCF
--------------------------------------	--------------------------------------	---